## Quality Control of Vibro-compacted Carbonate Sands by means of CPT

Dr. ir Patrick Mengé DEME – Head of geotechnics division - RMPE



Dredging, Environmental & Marine Engineering

TC211 Workshop - Cancun 2019



Rinker all alies

OUTLINE				TC 211
•	HYDRAULIC FILL	REQUIRE- MENTS	CARBONATE SAND	
	QUALITY CONTROL	CASE SARB	CONCLU- SIONS / CONSIDE- RATIONS	

\$

SIMSG ISSMGE

# Large land reclamation works – Hydraulic Fill





\$

## Large land reclamation works – Hydraulic Fill



SIMSG ISSMGE TC 211

- Massive sand placement by dredging equipment
- Quality depending on local availability (fines content, mineralogy, ...)
- Quality in part depending on dredging technique and segregation in reclamation
- (Relative) Densities depending on installation method and above or below water installation



### **Requirements**

#### ▼ Material



- Mineralogy (e.g. carbonates content)
- > Plasticity
- Relative density / Compaction
  - > Minimum relative density; may be different above and below water; often higher in top 1 or 2 m
  - > Target  $q_c$ -line
  - Liquefaction resistance FoS<sub>L</sub>
- Shear strength: friction angle  $\varphi'$
- Bearing Capacity under defined loads on foundations
- ► Settlements
  - > Overall settlements under (service) loads / Differential settlements
  - > Residual settlements (consolidation of natural layers; secondary settlements)
  - > Earthquake induced settlements



## **Requirements**





### **Ground Improvement**



Ground improvement techniques typically used for granular fill

- Vibroflotation
- Dynamic compaction
- ► RIC
- ► HEIC
- Roller compaction
- Stone columns

Technique selected depending on fill material characteristics, layer thickness and on requirement

QA: Measure execution parameters!

## **Carbonate sand**





#### Calcareous sand or Carbonate sand

- ► Sand with (broken) shells
- Sand particles are microscopic small shells or shell debris
- Sand particles are porous
- Sand particle density: test material or porous individual particles?
- ▶ Up to 100% CaCO<sub>3</sub>
- ▶ Minimum CaCO<sub>3</sub>-value?

Occurs in many places in the world Is locally available and has to be used



## **Carbonate sand**

Many different calcareous or carbonate sands are found in the world!







SIMSG | ISSMGE

**TC 211** 

\$



### Calcareous sand

# Some consequences

- Crushable material
- Effect on compaction: zone of influence / change in PSD / less permeable mantle around the probe
- Effect on testing: CPT / MDD / other?
- How to interpret CPT?
- How to perform lab testing: proctor vs vibratory table?
- Min and Max densities are lower in absolute value compared to silica sand: gives 'uncomfortable' feeling
- Effect on shear strength : angularity:  $\varphi' >>$
- Effect on stiffness : lower stiffness
- Effect on liquefaction potential : + or : is unclear
- Often fines are mineralogically the same non plastic material – product of particle degradation



total breakage, Bt = area BCDB breakage potential, Bp = area BCAB relative breakage, Br = Bt/Bp

% passing

0



Modified

proctor test

Standard proctor test





#### Sampling and shallow testing

- PSD attention not to further desintegrate the material
- In situ density Sand replacement method
- Defining MDD No dynamic tests; prefer vibratory table according to ASTM

#### **Deep testing**

- ► CPT with Shell Correction Factor
- ► BH with SPT SCF??? No literature available

#### Further evaluation based on CPT

- Material type and layering
- Relative density
- Liquefaction assessment





#### **CPT and Shell Correction Factor**

- ► SCF =  $q_{c,silica} / q_{c,carbonate}$
- Has been demonstrated by multiple researchers
- Depends on Carbonate sand type
- Depends on Relative density
- Depends on stress state
- Depends on Carbonates content
- Need for project dependent calibration
- Use of a constant value of 1.3 is not correct



#### **QC CPT in Vibroflotation practice**

- Compaction in triangular grid
- Quality control by means of CPT: where to perform?
- One CPT in center of grid: 'worst' location'
- One CPT at 1/3 distance between compaction points: 'best location'

Remark: Quality assurance during VC execution; measure all execution parameters – required power at end of each compaction level is good control parameter



SIMSG

**TC 211** 

## Evaluation of CPT's

- ► Analysis of CPT result presence of 'unsuitable' layers in the fill
- Allowable 'inclusions':
  - > Max layer thickness: 0.2m to 0.3m
  - Sum of all inclusions: max 10% to 15% of total fill thickness / sometimes not allowed above the water table or in top x m
  - > No influence on settlement and BC requirements
- ► CPT-handling for further analysis
  - Horizontal averaging; sometimes allowed only for relative density, not for liquefaction analysis

     is considered very conservative approach
  - Vertical running averaging (over 1m or 0.5m): is generally allowed but discussion wrt averaging height
- SBT I<sub>c</sub> parameter for fines content: not reliable! Always sampling needed for 'contractual' evaluation of fines content







#### CPT analysis for Soil Behavior Type I<sub>C</sub> TC 211

SIMSG

- No fully reliable link with fines content; is called 'apparent' fines content by Robertson
- Gives different result when one compares the I<sub>C</sub> from pre to post compaction CPT's
- Important factor for automatic liquefaction assessment
- One should combine pre compaction I<sub>C</sub> with post compaction CPT: how to do this?



## SARB ISLANDS CASE STUDY



SIMSG

R





S

## **Case study: Calibration chamber test results**



## **Case study: SCF**

- **F** Relative density definition is OK with site specific calibration: discussion solved
- Practical approach for liquefaction assessment: with SCF
- ▶ Is dependent on the relative density formula used (Jamiolkowski et al, 2001 is taken as reference)

SIMSG

ISSMGE

**TC 211** 

- Is dependent on the relative density and stress level
- ▶ What about dependence on PSD, C<sub>u</sub> or carbonates content? Mayne: when CC > 42% independent



#### **Case study - Post compaction CPT evaluation – relative density**

S2-11Q-130425-POST-0-003 / S2-11Q-130425-POST-3-004 ---

\_\_\_ Dr = 50%, w = 0,15% \_\_ Dr = 62%

Dr = 62%, w = 0,15%

- Dr = 82%, w = 0,15% (based on agreed correlation)

ISSMGE

SIMSG F





## **Conclusions / Considerations**

SIMSG ISSMGE TC 211

- Mineralogy of the reclamation material is important: need for CaCO<sub>3</sub>-content!
- Adapted quality control methods for specific crushing behavior
- Use of SCF: remains a point of discussion with client/consultant but also from theoretical point of view (for different reasons)
- Site Specific correlations for relative density will help for RD, not for liquefaction assessment
- Remain realistic when evaluating such large earthworks below and above the water table: allowance for 'unsuitable' inclusions; certain margin on 'non-conformity' is unavoidable unless 'clean' Borrow Area is found
- Preference for 'Performance Requirements': do not only focus on material testing, but overall behavior testing (e.g. zone load tests, embankment tests, ...)
- When one wants to avoid the use of SCF for liquefaction assessment: more advanced testing such as cyclic TX or cyclic DSS or in situ testing by means of Seismic CPT, PMT or DMT – need for further research in these fields with calcareous sands
- Liquefaction assessment: : why is Liquefaction Potential Index not used in practice (e.g. to overcome issues with limited thickness failing silty sand layers)?
- Engineering Review / Engineering Judgment remains key in these projects DEMET CREATING LAND FOR THE FUTURE

# Thank you for your attention



SIMSG

A